


**SEI** SMOLEN • EMR  
• ILKOVITCH  
ARCHITECTS

**MC  
PS**

# EASTERN MIDDLE SCHOOL FEASIBILITY STUDY

## Community Engagement Meeting No. 3

Translator service available  
*Servicio de traductor disponible*



April 29, 2025 at 7:00pm

# FOUR STEP PROCESS

## Step 2: Concept Design

### **Community Engagement Meeting #1**

Information gathering and evaluation meeting

**March 4, 2025 at 7pm**

### **Community Engagement Meeting #2**

Concept Design Meeting

**March 24, 2025 at 3pm**

### **Community Engagement Meeting #3 (Virtual)**

Developed plan option review meeting

**April 29, 2025 at 7pm**

### **Community Engagement Meeting #4 (Virtual)**

Review of final options

Evaluation of results, development of pro's and con's

**May 28, 2025 at 7pm**

## Agenda


- **Review**

- Meeting #1
- Meeting #2
- Stakeholder Priorities

- **Refined Approaches**

- Renewal  
(0% Demolition)
- Renovation / Addition  
(25% Demolition)
- Renovation / Addition  
(60% Demolition)
- Replacement A – Two Story  
(100% Demolition)
- Replacement B – Three Story  
(100% Demolition)

- **Next Steps**



**The purpose of a feasibility study is to determine the project approach, not to design the building**

# REVIEW

## Stakeholder Priorities

### • Building Goals

- Innovative Next Generation learning
- Safety, security & supervision
- Achieves Ed Spec program areas
- Adjacencies
- Proportions of learning spaces

### • Community

- Pedestrian access & safety
- Integration with surroundings
- Civic presence
- Welcoming environment
- Appropriate community use of building & site amenities

### • Cost

- Initial construction cost
- Life cycle / operation cost

### • Site


- Circulation (parking, parent loop patterns, service)
- Site programs (fields, courts, outdoor learning )

### • Sustainability

- Capacity to achieve Net Zero Ready
- Integrate sustainability into everyday use

### • Phased Occupied Construction


- Duration
- Impact on learning spaces
- Impact on site (circulation & fields)



# APPROACH 1: RENEWAL (0% DEMO)

## Parti

- Renovation
- Relocate drop-off / pick-up loop and parking along East Franklin Ave
- Rework bus loop
- Maintain exiting courtyard for educational opportunities
- Maintain location of play fields / courts
- Remove site circulation from civic front along University Blvd



# APPROACH 1: RENEWAL (0% DEMO)

## Site Plan

- Main entry adjacent bus loop, facing University Blvd and controlled by admin
- L2L on prominent exterior facade
- Gym adjacent play fields
- Service adjacent kitchen



# APPROACH 1: RENEWAL (0% DEMO)

## Site Circulation

### • Safe Access

- Separation of bus and automobile traffic
- Pedestrians from University Blvd do not cross any vehicle entrances
- Long stacking for parent drop-off
- No University Blvd Access
- Prominent bus loop closer to University Blvd






# APPROACH 1: RENEWAL (0% DEMO)

## Phasing


Phase	Year 1			Year 2			Year 3			Year 4			Year 5
	Summer	Fall	Spring	Summer	Fall	Spring	Summer	Fall	Spring	Summer	Fall	Spring	Summer
0% Demolition Concept - 2.5 year (3 Summer) Duration. Spring break completion													
1	Central Plant addition												
2				Cafeteria/Kitchen Reno									
3				PE Support Wing Reno									
4						Science Wing Reno							
5							Admin/Gym/Media Reno						
6							University Blvd Reno						
7				Pave Site			Pave Site						

Phase 1




New central plant renovation

Phase 2




Cafeteria/kitchen renovation

Phase 3




PE support wing renovation

Phase 4




Science wing renovation

Phase 5




Admin/gym/media center renovation

Phase 6



University Boulevard renovation

Building Complete




Building complete + site work

- Existing Building
- New Building
- Addition
- Renovation
- Demolition

# APPROACH 1: RENEWAL (0% DEMO)

## Pros & Cons



## PROS

### BUILDING/PLAN

- 20<sup>th</sup> century layout minimizes unprogrammed areas

### PHASED OCCUPIED CONSTRUCTION

- Shortest timeline of renovation concepts

### COMMUNITY

- Walkers do NOT cross any vehicle entrances

### SUSTAINABILITY

- Reuses ALL existing building steel and concrete

### COST

- Minimizes initial construction cost

## CONS

### BUILDING/PLAN

- LEAST next generation learning opportunities
- Long, narrow lab spaces within renovated building
- Media center not integrated with grade level clusters
- Sciences not integrated with grade level clusters
- Building services, Media Center, and Gym volume spaces are below Ed Spec standards

### SITE

- Least usable site program space

### COMMUNITY

- Main entrance faces away from University Blvd
- Playfields remain hidden, limiting afterhours use supervision


### SUSTAINABILITY

- May not be able to achieve Net Zero Ready

## APPROACH 2: REN/ADD (25% DEMO)

### Parti


- Renovation / Addition
- Relocate bus loop along University Blvd
- Relocate drop-off / pick-up loop and parking along East Franklin Ave
- Maintain exiting courtyard for educational opportunities
- Maintain location of play fields / courts
- Provide new civic front along University Blvd



# APPROACH 2: REN/ADD (25% DEMO)

## Site Plan

- Main entry adjacent bus loop, facing University Blvd and controlled by admin
- L2L on prominent exterior facade
- Gym adjacent play fields
- Service adjacent kitchen



# APPROACH 2: REN/ADD (25% DEMO)

## Site Circulation


### • Safe Access

- Separation of bus and automobile traffic
- Pedestrians from University Blvd cross bus traffic only
- Long stacking for parent drop-off
- No University Blvd Access
- Prominent bus loop closer to University Blvd



# APPROACH 2: REN/ADD (25% DEMO)

## Pros & Cons



### PROS

#### COMMUNITY

- Students do NOT cross drop of loop entrance
- Main parking lot behind school

#### SUSTAINABILITY

- Reuses MOST existing building steel and concrete

#### COST

- Moderates initial construction cost

### CONS

#### BUILDING/PLAN

- MINIMAL next generation learning opportunities
- Long, narrow lab spaces within renovated building
- Media center not integrated with grade level clusters
- Sciences not integrated with grade level clusters

#### PHASED OCCUPIED CONSTRUCTION

- Longest construction duration

#### COMMUNITY

- Main entrance faces away from University Blvd
- Playfields remain hidden, limiting afterhours use supervision


#### SUSTAINABILITY

- Large amount of site mounted PV to achieve Net Zero ready

# APPROACH 3: REN/ADD (60% DEMO)

## Parti


- Renovation / Addition
- Reconfigure drop-off / pick-up loop along University Blvd
- Reconfigure bus loop and parking along East Franklin Ave
- Maintain exiting courtyard for educational opportunities
- Maintain location of play fields / courts
- Provide new civic front along University Blvd



# APPROACH 3: REN/ADD (60% DEMO)

## Site Plan

- Main entry adjacent parent drop-off / pick-up, facing University Blvd and controlled by admin
- L2L on prominent exterior facade
- Gym adjacent play fields
- Service adjacent kitchen
  - Visible from E. Franklin Ave




# APPROACH 3: REN/ADD (60% DEMO)

## Site Circulation


### • Safe Access

- Separation of bus and automobile traffic
- Pedestrians from University Blvd cross automobile traffic
- Long stacking for parent drop-off
- No University Blvd Access



# APPROACH 3: REN/ADD (60% DEMO)

## Pros & Cons



### PROS

#### BUILDING/PLAN

- SOME ideal superteam layouts
- Media Center integrated with superteams

#### COMMUNITY

- Strong street presence for main entrance

#### SUSTAINABILITY

- Reuses MUCH existing building steel and concrete
- Sizeable area for rooftop PV array (not enough for full net-zero)

### CONS

#### BUILDING/PLAN

- P.E. program is remotely located
- Central plant, Kitchen and building services separated

#### SITE

- Kitchen loads from bus loop

#### PHASED OCCUPIED CONSTRUCTION

- Longest construction
- Select demolition of structural bays more structurally complicated

#### COMMUNITY

- Walkers cross drop off loop entrance
- Playfields remain hidden, limiting afterhours use supervision


#### SUSTAINABILITY

- Some site mounted PV to achieve Net Zero ready

# APPROACH 4: REPLACE (2 STORY)

Parti



- Replacement
- New bus loop between play fields and new building
- Drop-off / pick-up loop and parking on east side of new building
- Create new courtyard for educational opportunities
- Create new supervisable play fields along University Blvd



# APPROACH 4: REPLACE (2 STORY)

## Scope

- Existing Building: 152,030 GSF
- Demolition: 152,030 GSF (100%)
- Renovation: 0 GSF
- New Construction: 160,070 GSF
- Total Proposed Area: 160,070 GSF
  - Ed Spec NSF: 107,366
  - 67% Efficiency



# APPROACH 4: REPLACE (100% DEMO)

## Site Circulation

### • Safe Access


- Separation of bus and automobile traffic
- Pedestrians from University Blvd cross automobile traffic
- Long stacking for parent drop-off, away from University Blvd
- No University Blvd Access



# APPROACH 5: REPLACE (3 STORY)

Parti



- Replacement
- New bus loop between play fields and new building
- Drop-off / pick-up loop and parking on east side of new building
- Create new courtyard for educational opportunities
- Create new supervisable play fields along University Blvd



# APPROACH 5: REPLACE (3 STORY)

## Scope

- Existing Building: 152,030 GSF
- Demolition: 152,030 GSF (100%)
- Renovation: 0 GSF
- New Construction: 160,070 GSF
- Total Proposed Area: 160,070 GSF
  - Ed Spec NSF: 107,366
  - 67% Efficiency




# APPROACH 5: REPLACE (3 STORY)

## Site Circulation


### • Safe Access

- Separation of bus and automobile traffic
- Pedestrians from University Blvd do not cross any vehicle entrances
- Long stacking for parent drop-off, away from University Blvd



# APPROACH 5: REPLACE (3 STORY)

## Pros & Cons



### PROS

#### BUILDING/PLAN

- Idealized superteam layouts
- Media Center integrated with superteams

#### SITE

- Maximizes site programming area

#### PHASED OCCUPIED CONSTRUCTION

- Shortest Construction Duration
- No Portables or Modulares needed

#### COMMUNITY

- Playfields visible for afterhours use
- Walkers do NOT cross vehicle entrances
- School is most prominent, not car infrastructure

#### SUSTAINABILITY

- Net-Zero Ready

#### COST

- Lowest lifecycle / operational cost

### CONS

#### BUILDING/PLAN

- Longer travel distances with 3<sup>rd</sup> story

#### PHASED OCCUPIED CONSTRUCTION

- No playfields during construction

#### COMMUNITY

- Building closer to Curran Road
- 3 story footprint less cohesive with neighborhood

#### SUSTAINABILITY

- No reuse of existing steel or concrete